


SHEET PRINTED: 10/3/2024 11:40:44 AM



1

FIRST FLOOR ELECTRICAL AND PLUMBING DEMOLITION PLAN

1/4" = 1'-0"

GENERAL SHEET NOTES:

A. REFER TO E000 FOR ELECTRICAL SYMBOLS, ABBREVIATIONS, INSTALLATION NOTES, AND RENOVATION NOTES.

KEYNOTES:

1. ELECTRICAL CONDUIT FOR WALL MOUNTED TV SHALL BE DEMOLISHED.
2. REMOVE EXISTING BENCH TOP WIRE MOLD. RETAIN EXISTING BACKBOX AND WIRING FOR INSTALLATION OF NEW WIRE MOLD.
3. CONTRACTOR SHALL REMOVE ABANDONED HOT WATER COIL.
4. CONTRACTOR SHALL CUT AND CAP HW, CW, AND SAN LINES.
5. CONTRACTOR SHALL REMOVE ABANDONED COMPRESSED AIR LINES.
6. CONTRACTOR SHALL REMOVE HEATING WATER SUPPLY AND HEATING WATER RETURN LINES.
7. RETAIN EXISTING BACKBOXES AND WIRING FOR EXISTING RECEPTACLES FOR INSTALLATION OF NEW DEVICES IN THE ROOM. FOR MORE INFORMATION SEE E221.
8. REMOVE AND RETAIN EXISTING DEVICE FOR REINSTALLATION IN EXISTING LOCATION. REFER TO E222 FOR ADDITIONAL INFORMATION.
9. REMOVE AND RETAIN EXISTING DEVICE AND SURFACE RACEWAY FOR REINSTALLATION IN EXISTING LOCATION. REFER TO E222 FOR ADDITIONAL INFORMATION.
10. JUNCTION BOX AND ASSOCIATED CONDUIT SHALL BE DEMOLISHED.
11. AV CONDUIT AND ASSOCIATED WIRING FOR CEILING MOUNTED DEVICE SHALL BE DEMOLISHED.

DELV
DESIGN

P PURDUE
UNIVERSITY

LILY HALL TEACHING LAB 1-129 RENOVATION


ARCHITECT

DELV Design
212 W 10th St, STE F125
Indianapolis, IN 46202
(317) 296-7400

MEP

IMEG
8900 Keystone Crossing #210
Indianapolis, IN 46240
(317) 848-5045

100% CONSTRUCTION DOCUMENTS



Christopher J. Edwards

| No. | Description | Date |
|-----|-------------|------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

PROJECT #: 24005124.00
ISSUE DATE: 10.03.2024
DRW: RT | CHK: CJE

FIRST FLOOR MEP DEMOLITION PLAN

E101